

Pre-Stage
Equipment you can expect to see





Speed Swing

A rail-mounted piece of equipment that will move rail carts from the crane loading area to the sheet pile equipment and excavators.



Wheel Loader

Used to move materials and small equipment from the street and staging yard to the crane, which will then be hoisted up onto the embankment.




Backhoe

Used for digging, excavating and moving materials up on the tracks.



Tamper

Will be moved up onto the tracks and used to align the tracks before trains return to service.



Vibratory Sheet Pile Installer

Used to install sheet piling along the existing tracks during the excavation of the embankment for duct bank construction. Sheet piling is steel that is vibrated into the ground for earth retention purposes, holding the embankment in place and keeping construction workers and the existing structure safe.



Pre-Stage
Equipment you can expect to see